



Test Report

Product Name : Terminator P4
Model No. : AB-T2101

Applicant	:	ASUSTeK COMPUTER INC.
Address	:	4Fl., No. 150, Li-Te Rd., Peitou, Taipei, Taiwan, R.O.C.

Date of Receipt	:	Jan. 10, 2002
Date of Test	:	Jan. 23, 2002
Report No.	:	021L020E

The Test Results relate only to the samples tested.
The test report shall not be reproduced except in full without the written approval of Quietek Corporation.



Declaration of Conformity

The following products is herewith confirmed to comply with the requirements set out in the Council Directive on the Approximation of the laws of the Member States relating to Electromagnetic Compatibility Directive (89/336/EEC). The listed standard as below were applied:

The following Equipment:

Product : Terminator P4
Trade Name : ASUS
Model Number : AB-T2101

This product is herewith confirmed to comply with the requirements set out in the Council Directive on the Approximation of the laws of the Member States relating to Electromagnetic Compatibility Directive (89/336/EEC). For the evaluation regarding EMC, the following standards were applied:

RFI Emission:

EN 55022:1998 Class B : Product family standard
EN 61000-3-2:1995 Class D : Limits for harmonic current emission
Amendment 1:1998
Amendment 2:1998
Amendment 14:2000
EN 61000-3-3:1995 : Limitation of voltage fluctuation and flicker in low-voltage supply system

Immunity :

EN 55024:1998 Product family standard

The following importer/manufacturer is responsible for this declaration:

Company Name : _____
Company Address : _____
Telephone : _____ Facsimile : _____

Person is responsible for marking this declaration:

Name (Full Name)

Position/ Title

Date

Legal Signature



Quietek Corporation

EMC/Safety Test Laboratory
Accredited by DNV, TUV, Nemko and NVLAP

Date: Jan. 25, 2002
QTK No.: 0211.020E



Statement of Conformity

The certifies that the following designated product

Product : Terminator P4
Trade Name : ASUS
Model Number : AB-T2101
Company Name : ASUSTeK COMPUTER INC.

This product is herewith confirmed to comply with the requirements set out in the Council Directive on the Approximation of the laws of the Member States relating to Electromagnetic Compatibility Directive (89/336/EEC). For the evaluation regarding EMC, the following standards were applied:

RFI Emission:

EN 55022:1998 Class B : Product family standard

EN 61000-3-2:1995 Class D : Limits for harmonic current emission
Amendment 1:1998
Amendment 2:1998
Amendment 14:2000


EN 61000-3-3:1995 : Limitation of voltage fluctuation and flicker in low-voltage supply system

Immunity :

EN 55024:1998 Product family standard



TEST LABORATORY


Gene Chang/ Manager

The verification is based on a single evaluation of one sample of above-mentioned products. It does not imply an assessment of the whole production and does not permit the use of the test lab. Logo.

Test Report Certification

Test Date : Jan. 23, 2002

Report No. : 021L020E








Accredited by TUV, DNV, Nemko and NIST (NVLAP)



Product Name : Terminator P4
Applicant : ASUSTeK COMPUTER INC.
Address : 4Fl., No. 150, Li-Te Rd., Peitou, Taipei, Taiwan, R.O.C.
Manufacturer : ASUSTeK COMPUTER INC.
Model No. : AB-T2101
Rated Voltage : AC 230V/50Hz
Trade Name : ASUS
Measurement Standard : EN 55022:1998 Class B
EN 61000-3-2:1995, Amendment 1:1998, Amendment 2:1998
EN 61000-3-3:1995
EN 55024:1998
Measurement Procedure : EN 55022:1998, EN 61000-3-2:1995, EN 61000-3-3:1995,
IEC 61000-4-2:1995, IEC 61000-4-3:1995, IEC 61000-4-4:1995,
IEC 61000-4-5:1995, IEC 61000-4-6:1996, IEC 61000-4-8:1993,
IEC 61000-4-11:1994
Test Result : Complied



The Test Results relate only to the samples tested.

The test report shall not be reproduced except in full without the written approval of Quietek Corporation.

Documented By :  (Amy Hung)  

Tested By :  (Miller Lee) 

Reviewed By :  (Wallace Pan) 

Approved By :  (Gene Chang) 

Test Report Certification

Test Date: Jan. 23, 2002

Report No. : 021L020E



Accredited by NIST (NVLAP)

NVLAP Lab Code: 200533-0

Product Name : Terminator P4

Applicant : ASUSTeK COMPUTER INC.

Address : 4Fl., No. 150, Li-Te Rd., Peitou, Taipei, Taiwan, R.O.C.

Manufacturer : ASUSTeK COMPUTER INC.

Address : 4Fl., No. 150, Li-Te Rd., Peitou, Taipei, Taiwan, R.O.C.

Model No. : AB-T2101

Rated Voltage : Powered by PC

Trade Name : ASUS

Measurement Standard : AS/NZS 3548: 1995

Measurement Procedure : AS/NZS 3548: 1995

Classification : Class B

Test Result : Complied



The Test Results relate only to the samples tested.

The test report shall not be reproduced except in full without the written approval of Quietek Corporation.

This report must not be used to claim product endorsement by NVLAP any agency of the U.S. Government

Documented By : Amy Hung
(Amy Hung)

Tested By : Miller Lee
(Miller Lee)

Rebviewed By : Wallace Pan
(Wallace Pan)

Approved By : Gene Chang
(Gene Chang)

TABLE OF CONTENTS

Description	Page
1. General Information	6
1.1. EUT Description.....	6
1.2. Tested System Details.....	7
1.3. Configuration of tested System	8
1.4. EUT Exercise Software	10
1.5. Test Facility	11
2. Conducted Emission.....	12
2.1. Test Equipment List.....	12
2.2. Test Setup	12
2.3. Limits	13
2.4. Test Procedure	13
2.5. Test Specification	13
2.6. Test Result	13
3. Radiated Emission.....	14
3.1. Test Equipment.....	14
3.2. Test Setup	14
3.3. Limits	15
3.4. Test Procedure	15
3.5. Test Specification	15
3.6. Test Result	15
4. Power Harmonics and Voltage Fluctuation	16
4.1. Power Harmonics and Voltage Fluctuation Test Equipment List.....	16
4.2. Test Setup	16
4.3. Limits	16
4.4. Test Procedure	17
4.5. Test Specification	17
4.6. Test Result	17
5. Electrostatic Discharge (ESD).....	18
5.1. Test Equipment.....	18
5.2. Test Setup	18
5.3. Test Level	18
5.4. Test Procedure	19
5.5. Test Specification	19
5.6. Test Result	19
6. Radiated Susceptibility (RS).....	20
6.1. Test Equipment.....	20
6.2. Test Setup	20
6.3. Test Level	20
6.4. Test Procedure	21
6.5. Test Specification	21
6.6. Test Result	21
7. Electrical Fast Transient/Burst (EFT/B).....	22
7.1. Test Equipment.....	22
7.2. Test Setup	22
7.3. Test Level	22
7.4. Test Procedure	23
7.5. Test Specification	23
7.6. Test Result	23
8. Surge.....	24
8.1. Test Equipment.....	24
8.2. Test Setup	24

8.3.	Test Level	24
8.4.	Test Procedure	25
8.5.	Test Specification	25
8.6.	Test Result	25
9.	Conducted Susceptibility (CS).....	26
9.1.	Test Equipment.....	26
9.2.	Test Setup	26
9.3.	Test Level	27
9.4.	Test Procedure	27
9.5.	Test Specification	27
9.6.	Test Result	27
10.	Power Frequency Magnetic Field	28
10.1.	Test Equipment.....	28
10.2.	Test Setup	28
10.3.	Test Level	28
10.4.	Test Procedure	29
10.5.	Test Specification	29
10.6.	Test Result	29
11.	Voltage Dips and Interruption Measurement	30
11.1.	Test Equipment.....	30
11.2.	Test Setup	30
11.3.	Test Level	30
11.4.	Test Procedure	31
11.5.	Test Specification	31
11.6.	Test Result	31
12.	EMC Reduction Method During Compliance Testing.....	32
13.	Test Result	33
13.1.	Test Data of Conducted Emission	34
13.2.	Test Data of Radiated Emission	36
13.3.	Test Data of Power Harmonics.....	39
13.4.	Test Data of Electrostatic Discharge	42
13.5.	Test Data of Radiated Susceptibility	48
13.6.	Test Data of Electrical Fast Transient.....	50
13.7.	Test Data of Surge	52
13.8.	Test Data of Conducted Susceptibility	54
13.9.	Test Data of Power Frequency Magnetic Field	56
13.10.	Test Data of Voltage Dips and Interruption	58

ATTACHMENT 1: EUT TEST PHOTOGRAPHS

ATTACHMENT 2: EUT DETAILED PHOTOGRAPHS

REFERENCE : LABORATORY OF LICENSE

1. General Information

1.1. EUT Description

Product Name	:	Terminator P4
Trade Name	:	ASUS
Model No.	:	AB-T2101
Mother Board	:	ASUS, P4SC
CPU	:	P4 2.2GHz/100MHz
HDD	:	IBM, DILA-305044
CD-ROM	:	ASUS, CD-S520/A
FDD	:	ALPS ELECTRIC, DF354116F
VGA Card	:	On Board
Sound Card	:	On Board
Lan Card	:	On Board
Modem Card	:	ASKEY, MR MODEM PCI 56K
Switch Power Supply	:	HEC,Bestec, ATP-1655-NP
Power Cord	:	Non-Shielded, 1.8m

Note:

1. The PC System support Pentium III CPU the main measurement is 1.2GHz/133MHz detail as below:

Ports & Type	Quantity
PCI Slot	2
IDE Slot	2
Floppy	1
GamePort	1
COM Port	1
PS/2 Keyboard/Mouse Port	2
VGA	1
Printer	1
Line In	1
Line Out	2
Microphone	2
LAN	1
USB	4
Telephone In	1
Telephone Out	1

2. Quietek has verified the construction and function in typical operation. All the test modes were carried out with the EUT in normal operation, which was shown in this test report and defined as:

EMI Mode	:	Mode 1: Besteck, 1920*1440/75Hz
		Mode 2: HEC, 1920*1440/75Hz
EMS Mode	:	Mode 1: Besteck, 1920*1440/75Hz
		Mode 2: HEC, 1920*1440/75Hz

1.2. Tested System Details


The types for all equipment, plus descriptions of all cables used in the tested system (including inserted cards) are:

	Product	Manufacturer	Model No.	Serial No.
(1)	Monitor	SONY	CPD-G500	2738406
(2)	Modem	ACEEX	DM-1414	0102027553
(3)	Walkman	AIWA	HS-TA164	N/A
(4)	Microphone & Earphone	TOKTO	SX-MI	N/A
(5)	Keyboard	HP	SK-2506	C00083358
(6)	Earphone	AIWA	N/A	N/A
(7)	Microphone & Earphone	TOKTO	SX-MI	N/A
(8)	Mouse	IBM	M-SAU-IBM6	23-029359
(9)	USB Mouse	Logitech	M-BE58	LZE11403976
(10)	USB Mouse	Logitech	M-BE58	LZE11405150
(11)	USB Mouse	Logitech	M-BE58	LZE10151096
(12)	USB Mouse	Logitech	M-BE58	LZE11405267
(13)	Joystick	GENIUS	MAXFIRE FORCE G-09D	CJ0100200062
(14)	Telephone	Panasonic	KX-T7350X	N/A
(15)	Printer	EPSON	Color 680	015256
(16)	PC	IBM	2187-16W	BNL676C
(17)	Monitor	ADI	CM703	038054T10203891A
(18)	Keyboard	HP	SK-2506	C00083358
(19)	Mouse	IBM	M-SAU-IBM6	23-022641

Note : 1. The power cord of the device 1,15are 16 non-shielded power cord.

Signal Cable Type		Signal cable Description
A.	Modem Cable	Shielded, 1.2m
B.	Walkman Cable	Shielded, 1.5m
C.	Monitor Cable	Shielded, 1.8m, with ferrite core*2
D.	Earphone&Microphone Cable	Npn-Shielded, 2.0m
E.	Keyboard Cable	Shielded, 1.8m
F.	Mouse Cable	Shielded, 1.8m
G.	Earphone Cable	Non-shielded, 1.0m
H.	Mouse Cable	Shielded, 1.0m
I.	Earphone&Microphone Cable	Non-shielded, 2.0m
J.	Mouse Cable	Shielded, 1.0m
K.	Mouse Cable	Shielded, 1.8m
L.	Mouse Cable	Shielded, 1.8m
M.	Joystick Cable	Shielded, 1.8m
N.	Telephone Line	Non-Shielded, 2.0m
O.	Printer Cable	Shielded, 1.2m
P.	LAN Cable	Non-Shielded, 3.0m
Q.	Telephone Cable	Non-Shielded, 5.0m
R.	Monitor Cable	Shielded, 1.8m, with ferrite core
S.	Keyboard Cable	Shielded, 1.8m
T.	Mouse Cable	Shielded, 1.8m

1.3. Configuration of tested System



1.4. EUT Exercise Software

- (1) Setup the EUT and simulators as shown on 1.4.
- (2) Turn on the power of all equipment.
- (3) Personal Computer (EUT) reads data from disk.
- (4) EUT will sends "H" pattern to monitor, the monitor will show "H" pattern on the screen.
- (5) EUT sends "H" pattern to printer, the printer will print "H" pattern on paper.
- (6) EUT reads and writes data into and from modem.
- (7) EUT will read data from floppy disk and then writes the data into floppy disk, same operation for hard disk.
- (8) EUT Connect another simulation PC through LAN port and carry out Read/Write work each other.
- (9) Repeat the above procedure (3) to (7).
- (10) The CD ROM of EUT play the audio signal and video picture during the test.

1.5. Test Facility

Ambient conditions in the laboratory:

Items	Required (IEC 68-1)	Actual
Temperature (°C)	15-35	20-35
Humidity (%RH)	25-75	50-65
Barometric pressure (mbar)	860-1060	950-1000

Site Description:

June 29, 2001 Accreditation on NVLAP
 NVLAP Lab Code: 200347-0



June 11, 2001 Accreditation on DNV
 Statement No. : 413-99-LAB11



January 04, 1999 Accreditation on TUV Rheinland
 Certificate No.: I9865712-9901



April 18, 2001 Accreditation on Nemko
 Certificate No.: ELA 165
 Certificate No.: ELA 162



Site Name: Quietek Corporation

Site Address: N0.5-22, Ruei-Shu Valley, Rue-Ping Tsuen, Lin Kou
 Shiang, Taipei 244, Taiwan, R.O.C.

TEL : 886-2-8601-3788 / FAX : 886-2-8601-3789

E-Mail : service@quietek.com

2. Conducted Emission


2.1. Test Equipment List

The following test equipment are used during the conducted emission test:

Item	Instrument	Manufacturer	Type No./Serial No	Last Cal..	Remark
1	Test Receiver	R & S	ESCS 30/838251/0001	May, 2001	
2	L.I.S.N.	R & S	ESH3-Z5/836679/0023	May, 2001	EUT
3	L.I.S.N.	R & S	ENV 4200/833209/0023	May, 2001	Peripherals
4	Pulse Limiter	R & S	ESH3-Z2	May, 2001	
5	N0.4 Shielded Room			N/A	

Note: All equipment upon which need to calibrated are with calibration period of 1 year.

2.2. Test Setup



2.3. Limits

EN 55022 Limits (dBuV)				
Frequency MHz	Class A		Class B	
	QP	AV	QP	AV
0.15 - 0.50	79	66	66-56	56-46
0.50-5.0	73	60	56	46
5.0 - 30	73	60	60	50

Remarks : In the above table, the tighter limit applies at the band edges.

2.4. Test Procedure

The EUT and simulators are connected to the main power through a line impedance stabilization network (L.I.S.N.). This provides a 50 ohm /50uH coupling impedance for the measuring equipment. The peripheral devices are also connected to the main power through a LISN that provides a 50ohm /50uH coupling impedance with 50ohm termination. (Please refers to the block diagram of the test setup and photographs.)

Both sides of A.C. line are checked for maximum conducted interference. In order to find the maximum emission, the relative positions of equipment and all of the interface cables must be changed according to EN 55022:1998 on conducted measurement.

Conducted emissions were investigated over the frequency range from 0.15MHz to 30MHz using a receiver bandwidth of 9kHz.

2.5. Test Specification

According to EN 55022:1998

2.6. Test Result

The emission from the EUT was below the specified limits. The worst-case emissions are shown in section 13. The acceptance criterion was met and the EUT passed the test.

3. Radiated Emission


3.1. Test Equipment

The following test equipment are used during the radiated emission test:

Test Site	Equipment	Manufacturer	Model No./Serial No.	Last Cal.
<input type="checkbox"/> Site # 1	X Test Receiver	R & S	ESVS 10 / 834468/003	July, 2001
	X Spectrum Analyzer	Advantest	R3162/ 00803480	May, 2001
	X Pre-Amplifier	Advantest	BB525C/ 3307A01812	May, 2001
	X Bilog Antenna	SCHAFFNER	CBL6112B / 2697	Nov., 2000
	X Test Receiver	R & S	ESCS 30 / 836858/022	Nov., 2001
<input checked="" type="checkbox"/> Site # 2	X Spectrum Analyzer	Advantest	3162 / 100803466	May, 2001
	X Pre-Amplifier	Advantest	BB525C/3307A01814	May, 2001
	X Bilog Antenna	SCHAFFNER	CBL6112B / 2705	Oct., 2001
	X Horn Antenna	ETS	3115 / 0005-6160	July, 2001
	X Pre-Amplifier	QTK	QTK-AMP-01/ 0001	July, 2001

- Note:
1. All equipments that need to calibrate are with calibration period of 1 year.
 2. Mark "X" test instruments are used to measure the final test results.

3.2. Test Setup



3.3. Limits

EN 55022 Limits (dBuV)				
Frequency MHz	Class A		Class B	
	Distance (m)	dBuV/m	Distance (m)	dBuV/m
30 – 230	10	40	10	30
230 – 1000	10	47	10	37

3.4. Test Procedure

The EUT and its simulators are placed on a turn table which is 0.8 meter above ground. The turn table can rotate 360 degrees to determine the position of the maximum emission level. The EUT was positioned such that the distance from antenna to the EUT was 10 meters.

The antenna can move up and down between 1 meter and 4 meters to find out the maximum emission level.

Both horizontal and vertical polarization of the antenna are set on measurement. In order to find the maximum emission, all of the interface cables must be manipulated according to EN55022:1998 on radiated measurement.

Radiated emissions were investigated over the frequency range from 30MHz to 1GHz using a receiver bandwidth of 120kHz. Radiated was performed at an antenna to EUT distance of 10 meters.

3.5. Test Specification

According to EN 55022:1998

3.6. Test Result

The emission from the EUT was below the specified limits. The worst-case emissions are shown in section 13. The acceptance criterion was met and the EUT passed the test.


4. Power Harmonics and Voltage Fluctuation

4.1. Power Harmonics and Voltage Fluctuation Test Equipment List

Item	Instrument	Manufacturer	Type No/Serial No.	Last Calibration
1	Power Harmonics Tester	SCHAFFNER	Proflin 2105-400 S/N: HK54148	Jun., 2001
2	Analyzer	SCHAFFNER	CCN 1000-1/X71887	Jun., 2001
3	No.3 Shielded Room			N/A

Note: All equipment upon which need to calibrated are with calibration period of 1 year.

4.2. Test Setup



4.3. Limits

➤Limits of Harmonics Currents

Harmonics Order	Maximum Permissible harmonic current (in amperes)	Harmonics Order	Maximum Permissible harmonic current (in amperes)
Odd harmonics		Even harmonics	
3	2.30	2	1.08
5	1.14	4	0.43
7	0.77	6	0.30
9	0.40	8 ≤ n ≤ 40	0.23 * 8/n
11	0.33		
13	0.21		
15 ≤ n ≤ 39	0.15 * 15/n		

4.4. Test Procedure

The EUT is supplied in series with power analyzer from a power source having the same normal voltage and frequency as the rated supply voltage and the equipment under test. And the rated voltage at the supply voltage of EUT of 0.94 times and 1.06 times shall be performed.

4.5. Test Specification

According to EN 61000-3-2:1995, , Amendment 1:1998, Amendment 2:1998 and EN 61000-3-3:1995

4.6. Test Result

The measurement of the power harmonics, which test at the extremes of EUT's supply range, was investigated and test result was shown in section 13. The acceptance criterion was met and the EUT passed the test.


5. Electrostatic Discharge (ESD)

5.1. Test Equipment

Item	Instrument	Manufacturer	Type No/Serial No.	Last Calibration
1	ESD Simulator System	SCHAFFNER	NSG 432 S/N: 1453	Jun., 2001
2	Horizontal Coupling Plane(HCP)	Quietek	HCP AL50	Jun., 2001
3	Vertical Coupling Plane(VCP)	Quietek	VCP AL50	Jun., 2001
4	No.1 Shielded Room			N/A

Note: All equipment upon which need to calibrated are with calibration period of 1 year.

5.2. Test Setup



5.3. Test Level

Item	Environmental Phenomena	Units	Test Specification	Performance Criteria
Enclosure Port				
	Electrostatic Discharge	kV(Charge Voltage)	8 Air Discharge 4 Contact Discharge	B

5.4. Test Procedure

Direct application of discharges to the EUT:

Contact discharge was applied only to conductive surfaces of the EUT.

Air discharges were applied only to non-conductive surfaces of the EUT.

During the test, it was performed with single discharges. For the single discharge time between successive single discharges will be keep longer 1 second. It was at least ten single discharges with positive and negative at the same selected point.

The selected point, which was performed with electrostatic discharge, was marked on the red label of the EUT.

Indirect application of discharges to the EUT:

Vertical Coupling Plane (VCP):

The coupling plane, of dimensions 0.5m x 0.5m, is placed parallel to, and positioned at a distance 0.1m from, the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge. It was at least ten single discharges with positive and negative at the same selected point.

Horizontal Coupling Plane (HCP):

The coupling plane is placed under to the EUT. The generator shall be positioned vertically at a distance of 0.1m from the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge. It was at least ten single discharges with positive and negative at the same selected point.

5.5. Test Specification

According to EN 61000-4-2:1995

5.6. Test Result

The measurement of the electrostatic discharge was investigated and test result was shown in section 13. The acceptance criterion was met and the EUT passed the test.


6. Radiated Susceptibility (RS)

6.1. Test Equipment

Item	Instrument	Manufacturer	Type No/Serial No.	Last Calibration
1	Signal Generator	IFR	2023B / 202302/581	May, 2001
2	Power Amplifier	A & R	500A100AM3 /29369	Aug., 2001
3	Power Amplifier	SCHAFFNER	CBA9413B / 0006	June, 2001
4	Field Strength Sensor	SCHAFFNER	EMC 20 / Y-0028/ Z-0003	June, 2001
5	Power Antenna	SCHWARZBECK	VULB 9166 / 1073	Sep., 2001
6	Power Meter	BOONTON	4232A / 42201	May, 2001
7	No.2 EMC Fully Chamber			July, 2001

Note: All equipment upon which need to calibrated are with calibration period of 1 year.

6.2. Test Setup



6.3. Test Level

Item	Environmental Phenomena	Units	Test Specification	Performance Criteria
Enclosure Port				
	Radio-Frequency	MHz	80-1000	
	Electromagnetic Field	V/m(Un-modulated, rms)	3	A
	Amplitude Modulated	% AM (1kHz)	80	

6.4. Test Procedure

The EUT and load, which are placed on a table that is 0.8 meter above ground, are placed with one coincident with the calibration plane such that the distance from antenna to the EUT was 3 meters.

Both horizontal and vertical polarization of the antenna and four sides of the EUT are set on measurement.

In order to judge the EUT performance, a CCD camera is used to monitor EUT screen.

All the scanning conditions are as follows:

Condition of Test	Remarks
EN 55024:1998	
1. Field Strength	3 V/M Level 2
2. Radiated Signal	AM 80% Modulated with 1kHz
3. Scanning Frequency	80MHz - 1000MHz
4 Dwell Time	3 Seconds
5. Frequency step size Δf :	1%
6. The rate of Swept of Frequency	1.5×10^{-3} decades/s

6.5. Test Specification

According to EN 61000-4-3:1995

6.6. Test Result

The measurement of the radiated susceptibility was investigated and test result was shown in section 13. The acceptance criterion was met and the EUT passed the test.


7. Electrical Fast Transient/Burst (EFT/B)

7.1. Test Equipment

Item	Instrument	Manufacturer	Type No/Serial No.	Last Calibration
1	Fast Transient/Burst Generator	SCHAFFNER	BEST S/N: 300035-008SC	Jun., 2001
2	No.3 Shielded Room			N/A

Note: All equipment upon which need to calibrated are with calibration period of 1 year.

7.2. Test Setup



7.3. Test Level

Item	Environmental Phenomena	Units	Test Specification	Performance Criteria
Signal Ports and Telecommunication Ports				
	Fast Transients Common Mode	kV (Peak) Tr/Ts ns Rep. Frequency kHz	0.5 5/50 5	B
Input DC Power Ports				
	Fast Transients Common Mode	kV (Peak) Tr/Ts ns Rep. Frequency kHz	0.5 5/50 5	B
Input AC Power Ports				
	Fast Transients Common Mode	kV (Peak) Tr/Ts ns Rep. Frequency kHz	1 5/50 5	B

7.4. Test Procedure

The EUT and load are placed on a table that is 0.8 meter above a metal ground plane measured 1m*1m min. and 0.65mm thick min. And projected beyond the EUT by at least 0.1m on all sides.

For Signal Ports and Telecommunication Ports:

The EFT interference signal is through a coupling clamp device couples to the signal and control lines of the EUT with burst noise for 1min.

For Input DC and AC Power Ports:

The EUT is connected to the power mains through a coupling device that directly couples the EFT interference signal.

Each of the Line and Neutral conductors is impressed with burst noise for 1 min.

The length of power cord between the coupling device and the EUT shall be 1m.

7.5. Test Specification

According to EN 61000-4-4:1995

7.6. Test Result

The measurement of the Electrical Fast Transient/Burst was investigated and test result was shown in section 13. The acceptance criterion was met and the EUT passed the test.


8. Surge

8.1. Test Equipment

Item	Instrument	Manufacturer	Type No/Serial No.	Last Calibration
1	Surge Generator	SCHAFFNER	BEST S/N: 300035-008SC	Jun., 2001
2	No.3 Shielded Room			N/A

Note: All equipment upon which need to calibrated are with calibration period of 1 year.

8.2. Test Setup



8.3. Test Level

Item	Environmental Phenomena	Units	Test Specification	Performance Criteria
Signal Ports and Telecommunication Ports				
	Surges	Tr/Ts uS	1.2/50 (8/20)	
	Line to Ground	KV	± 1	B
Input DC Power Ports				
	Surges	Tr/Ts uS	1.2/50 (8/20)	
	Line to Ground	kV	± 0.5	B
AC Input and AC Output Power Ports				
	Surges	Tr/Ts uS	1.2/50 (8/20)	
	Line to Line	kV	± 1	B
	Line to Ground	kV	± 2	

8.4. Test Procedure

The EUT and its load are placed on a table that is 0.8 meter above a metal ground plane measured 1m*1m min. and 0.65mm thick min. And projected beyond the EUT by at least 0.1m on all sides. The length of power cord between the coupling device and the EUT shall be 2m or less.

For Input and Output AC Power or DC Input and DC Output Power Ports:

The EUT is connected to the power mains through a coupling device that directly couples the Surge interference signal.

The surge noise shall be applied synchronized to the voltage phase at 0° , 90° , 180° , 270° and the peak value of the a.c. voltage wave. (Positive and negative)

Each of Line-Earth and Line-Line is impressed with a sequence of five surge voltages with interval of 1 min.

8.5. Test Specification

According to EN 61000-4-5:1995

8.6. Test Result

The measurement of the Surge was investigated and test result was shown in section 13. The acceptance criterion was met and the EUT passed the test.


9. Conducted Susceptibility (CS)

9.1. Test Equipment

Item	Instrument	Manufacturer	Type No/Serial No.	Last Calibration
1	Signal Generator	IFR	2023B / 202302/581	May, 2001
2	Power Amplifier	A & R	500A100AM3 /29369	Aug., 2001
3	Power Amplifier	SCHAFFNER	CBA9413B / 0006	June, 2001
4	CDN 1	Schwarzbeck	L801 M2/3 / 1549	Jun, 2001
5	CDN 2	Schwarzbeck	L801 S1 / 1574	Jun, 2001
6	CDN 3	Schwarzbeck	L801 AF4 / 1064	Jun, 2001
7	CDN 4	Schwarzbeck	L801 AF8 / 1070	Jun, 2001
8	CDN 5	FCC	FCC-801-S9 / 9837	Jun, 2001
9	CDN 6	FCC	FCC-801-S15 / 9838	Jun, 2001
10	CDN 7	FCC	FCC-801-S25 / 9839	Jun, 2001
11	50 ohm Terminator	RES-NET	RCX6BM	Jun, 2001
12	6dB Attenuator	BIRD	RFA250NFF10	Jun, 2001
13	EM Clamp	Schwarzbeck	KEMZ 801 / 15928	Jun, 2001
14	No.2 EMC Fully Chamber			N/A

Note: All equipment upon which need to calibrated are with calibration period of 1 year.

9.2. Test Setup



9.3. Test Level

Item	Environmental Phenomena	Units	Test Specification	Performance Criteria
Signal Ports and Telecommunication Ports				
	Radio-Frequency	MHz	0.15-80	
	Continuous Conducted	V (rms, Un-modulated)	3	A
		% AM (1kHz)	80	
Input DC Power Ports				
	Radio-Frequency	MHz	0.15-80	
	Continuous Conducted	V (rms, Un-modulated)	3	A
		% AM (1kHz)	80	
Input AC Power Ports				
	Radio-Frequency	MHz	0.15-80	
	Continuous Conducted	V (rms, Un-modulated)	3	A
		% AM (1kHz)	80	

9.4. Test Procedure

The EUT are placed on a table that is 0.8 meter height, and a Ground reference plane on the table, EUT are placed upon table and use a 10cm insulation between the EUT and Ground reference plane.

For Signal Ports and Telecommunication Ports

The disturbance signal is through a coupling and decoupling networks (CDN) or EM-clamp device couples to the signal and Telecommunication lines of the EUT.

For Input DC and AC Power Ports

The EUT is connected to the power mains through a coupling and decoupling networks for power supply lines. And directly couples the disturbances signal into EUT.

Used CDN-M2 for two wires or CDN-M3 for three wires.

All the scanning conditions are as follows:

Condition of Test	Remarks
1. Field Strength	130dBuV(3V) Level 2
2. Radiated Signal	AM 80% Modulated with 1kHz
3. Scanning Frequency	0.15MHz – 80MHz
4 Dwell Time	3 Seconds
5. Frequency step size Δf :	1%
6. The rate of Swept of Frequency	1.5×10^{-3} decades/s

9.5. Test Specification

According to EN 61000-4-6:1996

9.6. Test Result

The measurement of the Conducted Susceptibility was investigated and test result was shown in section 13. The acceptance criterion was met and the EUT passed the test.


10. Power Frequency Magnetic Field

10.1. Test Equipment

Item	Instrument	Manufacturer	Type No/Serial No.	Last Calibration
1	Voltage Dips Generator	Haefely	PLINE 1610 S/N: 080 938-05	Jun., 2001
2	Gauss Meter	F.W.BELL	4090	Jun., 2001
3	No.3 Shielded Room			N/A

Note: All equipment upon which need to calibrated are with calibration period of 1 year.

10.2. Test Setup



10.3. Test Level

Item	Environmental Phenomena	Units	Test Specification	Performance Criteria
Enclosure Port				
	Power-Frequency Magnetic Field	50 1	Hz A/m (r.m.s.)	A

10.4. Test Procedure

The EUT and its load are placed on a table which is 0.8 meter above a metal ground plane measured at least 1m*1m min. The test magnetic field shall be placed at central of the induction coil.

The test magnetic Field shall be applied 10minutes by the immersion method to the EUT. And the induction coil shall be rotated by 90° in order to expose the EUT to the test field with different orientation (X, Y, Z Orientations).

10.5. Test Specification

According to EN 61000-4-8:1993

10.6. Test Result

The measurement of the Power Frequency Magnetic Field was investigated and test result was shown in section 13. The acceptance criterion was met and the EUT passed the test.


11. Voltage Dips and Interruption Measurement

11.1. Test Equipment

Item	Instrument	Manufacturer	Type No/Serial No.	Last Calibration
1	Voltage Dips Generator	Haefely	PLINE 1610 S/N: 080 938-05	Jun., 2001
2	No.3 Shielded Room			N/A

Note: All equipment upon which need to calibrated are with calibration period of 1 year.

11.2. Test Setup



11.3. Test Level

Item	Environmental Phenomena	Units	Test Specification	Performance Criteria
Input AC Power Ports				
Voltage Dips		>95	% Reduction	B
		0.5	Period	
		30	% Reduction	C
25	Periods			
Voltage Interruptions		> 95	% Reduction	C
		250	Periods	

11.4. Test Procedure

The EUT and its load are placed on a table which is 0.8 meter above a metal ground plane measured 1m*1m min. And 0.65mm thick min. And projected beyond the EUT by at least 0.1m on all sides. The power cord shall be used the shortest power cord as specified by the manufacturer.

For Voltage Dips/ Interruptions test:

The selection of test voltage is based on the rated power range. If the operation range is large than 20% of lower power range, both end of specified voltage shall be tested. Otherwise, the typical voltage specification is selected as test voltage.

The EUT is connected to the power mains through a coupling device that directly couples to the Voltage Dips and Interruption Generator.

The EUT shall be tested for 30% voltage dip of supplied voltage and duration 10ms, for 60% voltage dip of supplied voltage and duration 100ms with a sequence of three voltage dips with intervals of 10 seconds, and for 95% voltage interruption of supplied voltage and duration 5000ms with a sequence of three voltage interruptions with intervals of 10 seconds. Voltage phase shifting are shall occur at 0° , 45° , 90° , 135° , 180° , 225° , 270° , 315° of the voltage.

11.5. Test Specification

According to EN 61000-4-11:1994

11.6. Test Result

The measurement of the Voltage Dips and Interruption was investigated and test result was shown in section 13. The acceptance criterion was met and the EUT passed the test.

12. EMC Reduction Method During Compliance Testing

No modification was made during testing.

13. Test Result

The test results in the emission and the immunity were performed according to the requirements of measurement standard and process. Quietek Corporation is assumed full responsibility for the accuracy and completeness of these measurements. The test data of the emission is listed as below.

All the tests were carried out with the EUT in normal operation, which was defined as:

EMI Mode	:	Mode 1: Besteck, 1920*1440/75Hz
		Mode 2: HEC, 1920*1440/75Hz
EMS Mode	:	Mode 1: Besteck, 1920*1440/75Hz
		Mode 2: HEC, 1920*1440/75Hz

Note :

- No Deviation from standard procedure
- Deviations from standard procedure

13.1. Test Data of Conducted Emission

Date of Test	Jan. 23, 2002	Test Room	No.4 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Line1 & Line2	Test Range	0.15MHz – 30MHz

Frequency MHz	Measurement Level (dBuV)				Limits (dBuV)	
	Line1 QP	Line1 AV	Line2 QP	Line2 AV	QP	AV
0.163	--	--	53.21	49.71	65.31	55.31
0.173	50.81	48.21	--	--	64.79	54.79
0.216	46.43	41.11	--	--	62.96	52.96
0.216	--	--	47.90	43.11	62.96	52.96
0.271	40.88	38.01	--	--	61.08	51.08
0.271	--	--	42.21	39.61	61.08	51.08
8.002	39.98	35.82	--	--	60.00	50.00
8.002	--	--	40.16	36.22	60.00	50.00
10.001	41.32	31.73	--	--	60.00	50.00
10.001	--	--	36.57	30.83	60.00	50.00
20.002	--	--	30.83	25.34	60.00	50.00
20.005	44.08	38.24	--	--	60.00	50.00

Note:

1. All Reading Levels are Quasi-Peak and average value.
2. Measurement Level = Reading Level + LISN Factor + Cable loss.
3. "--", means the average measurement was not performed when the Quasi-Peak measured data under the limit of average detection.

Date of Test	Jan. 23, 2002	Test Room	No.4 Shielded Room
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Line1 & Line2	Test Range	0.15MHz – 30MHz

Frequency MHz	Measurement Level (dBuV)				Limits (dBuV)	
	Line1 QP	Line1 AV	Line2 QP	Line2 AV	QP	AV
0.166	54.46	50.18	--	--	65.18	55.18
0.170	--	--	49.20	46.01	64.98	54.98
0.224	38.54	35.41	--	--	62.66	52.66
0.224	--	--	38.42	31.61	62.66	52.66
8.002	41.18	37.02	--	--	60.00	50.00
8.002	--	--	40.97	36.52	60.00	50.00
9.943	--	--	30.83	21.73	60.00	50.00
10.002	41.04	34.83	--	--	60.00	50.00
14.849	--	--	31.53	26.51	60.00	50.00
16.002	38.01	32.32	--	--	60.00	50.00
20.002	--	--	43.84	40.14	60.00	50.00
20.005	44.44	36.74	--	--	60.00	50.00

Note:

1. All Reading Levels are Quasi-Peak and average value.
2. Measurement Level = Reading Level + LISN Factor + Cable loss.
3. "--", means the average measurement was not performed when the Quasi-Peak measured data under the limit of average detection.


13.2. Test Data of Radiated Emission

Date of Test	Jan. 23, 2002	Test Site	No.2 OATS
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	10m & Horizontal	Test Range	30MHz – 1GHz

Frequency MHz	Cable Loss (dB)	Probe Factor (dB/m)	Pre-Amp Factor (dB)	Reading Level (dBuV/m)	Emission Level (dBuV/m)	Margin (dB)	Limit (dBuV/m)
56.520	1.00	5.93	0.00	11.62	18.55	11.45	30
61.440	1.03	5.29	0.00	15.68	22.00	8.00	30
66.340	1.05	5.66	0.00	13.21	19.92	10.08	30
87.187	1.16	9.46	0.00	12.60	23.22	6.78	30
125.000	1.36	11.64	0.00	9.80	22.80	7.20	30
175.000	1.62	8.56	0.00	12.68	22.86	7.14	30
415.230	2.85	15.67	0.00	14.60	33.12	3.88	37
458.190	3.07	16.48	0.00	14.23	33.78	3.22	37
558.415	3.59	17.51	0.00	10.60	31.70	5.30	37
787.500	4.77	19.21	0.00	8.21	32.19	4.81	37
859.087	5.15	19.72	0.00	6.60	31.47	5.53	37

Note:

1. All Reading Levels below 1GHz are Quasi-Peak.
2. Emission Level = Reading Level + Probe Factor + Cable loss – Preamp.
3. Margin = Limit - Emission Level Emission Level-Limit




Date of Test	Jan. 23, 2002	Test Site	No.2 OATS
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	10m & Vertical	Test Range	30MHz – 1GHz

Frequency MHz	Cable Loss (dB)	Probe Factor (dB/m)	Pre-Amp Factor (dB)	Reading Level (dBuV/m)	Emission Level (dBuV/m)	Margin (dB)	Limit (dBuV/m)
56.526	1.00	5.60	0.00	19.86	26.46	3.54	30
61.440	1.03	5.25	0.00	18.89	25.17	4.83	30
84.217	1.15	7.66	0.00	17.89	26.70	3.30	30
86.960	1.16	8.06	0.00	17.65	26.87	3.13	30
125.000	1.36	10.19	0.00	14.52	26.07	3.93	30
192.000	1.70	8.08	0.00	11.86	21.64	8.36	30
386.600	2.71	15.31	0.00	15.23	33.25	3.75	37
458.190	3.07	16.52	0.00	14.30	33.89	3.11	37
558.410	3.59	19.21	0.00	9.10	31.90	5.10	37
758.850	4.62	20.48	0.00	7.60	32.70	4.30	37
787.496	4.77	19.66	0.00	7.50	31.93	5.07	37
859.087	5.15	19.26	0.00	6.20	30.61	6.39	37

Note:

1. All Reading Levels below 1GHz are Quasi-Peak.
2. Emission Level = Reading Level + Probe Factor + Cable loss – Preamp.
3. Margin = Limit - Emission Level Emission Level-Limit




Date of Test	Jan. 23, 2002	Test Site	No.2 OATS
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	10m & Horizontal	Test Range	30MHz – 1GHz

Frequency MHz	Cable Loss (dB)	Probe Factor (dB/m)	Pre-Amp Factor (dB)	Reading Level (dBuV/m)	Emission Level (dBuV/m)	Margin (dB)	Limit (dBuV/m)
56.530	1.00	5.93	0.00	11.43	18.36	11.64	30
61.440	1.03	5.29	0.00	12.80	19.12	10.88	30
84.530	1.15	8.50	0.00	11.40	21.05	8.95	30
125.000	1.36	11.64	0.00	10.30	23.30	6.70	30
175.000	1.62	8.56	0.00	13.20	23.38	6.62	30
196.584	1.73	8.20	0.00	12.80	22.73	7.27	30
386.590	2.71	13.96	0.00	11.70	28.37	8.63	37
415.225	2.85	15.67	0.00	14.50	33.02	3.98	37
458.180	3.07	16.48	0.00	14.36	33.91	3.09	37
558.410	3.59	17.51	0.00	9.30	30.40	6.60	37
787.499	4.77	19.21	0.00	7.76	31.74	5.26	37
859.088	5.15	19.72	0.00	6.51	31.38	5.62	37

Note:

1. All Reading Levels below 1GHz are Quasi-Peak.
2. Emission Level = Reading Level + Probe Factor + Cable loss – Preamp.
3. Margin = Limit - Emission Level




Date of Test	Jan. 23, 2002	Test Site	No.2 OATS
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	10m & Vertical	Test Range	30MHz – 1GHz

Frequency MHz	Cable Loss (dB)	Probe Factor (dB/m)	Pre-Amp Factor (dB)	Reading Level (dBuV/m)	Emission Level (dBuV/m)	Margin (dB)	Limit (dBuV/m)
49.995	0.97	6.60	0.00	18.86	26.43	3.57	30
56.525	1.00	5.60	0.00	20.15	26.75	3.25	30
61.442	1.03	5.25	0.00	18.85	25.13	4.87	30
125.000	1.36	10.19	0.00	14.86	26.41	3.59	30
175.000	1.62	8.52	0.00	16.43	26.57	3.43	30
192.000	1.70	8.08	0.00	11.60	21.38	8.62	30
357.954	2.56	14.12	0.00	11.30	27.98	9.02	37
386.591	2.71	15.31	0.00	14.30	32.32	4.68	37
458.180	3.07	16.52	0.00	14.30	33.89	3.11	37
558.408	3.59	19.21	0.00	8.67	31.47	5.53	37
758.860	4.62	20.48	0.00	7.35	32.45	4.55	37
859.090	5.15	19.26	0.00	5.60	30.01	6.99	37

Note:

1. All Reading Levels below 1GHz are Quasi-Peak.
2. Emission Level = Reading Level + Probe Factor + Cable loss – Preamp.
3. Margin = Limit - Emission Level Emission Level-Limit




Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Power Harmonics (Classification : Class D)		

Test Result: Pass

Source qualification: Distortion


Current & voltage waveforms

It is 0.8% outside Class-D envelope



Harmonics and Class D limit line

European Limits



Test result: Pass

Worst harmonic was #3 with 99 % of the limit.

Current Test Result Summary (Run time)

Test Result: Pass

Source qualification: Distortion

Highest parameter values during test:

V_RMS (Volts): 224.03	I_RMS (Amps): 0.501
I_Peak (Amps): 1.198	Crest Factor: 2.549
I_Fund (Amps): 0.389	Power Factor: 0.772
Power (Watts): 87	

Harm#	Harmonics	Limit	% of Limit	Status
2	0.008			
3	0.285	0.287	99.00	Pass
4	0.006			
5	0.136	0.161	84.06	Pass
6	0.005			
7	0.046	0.084	55.44	Pass
8	0.004			
9	0.032	0.043	74.29	Pass
10	0.002			
11	0.016	0.028	58.91	Pass
12	0.001			
13	0.013	0.027	49.19	Pass
14	0.001			
15	0.010	0.023	41.86	Pass
16	0.001			
17	0.007	0.020	36.70	Pass
18	0.001			
19	0.007	0.018	36.22	Pass
20	0.001			
21	0.005	0.016	34.06	Pass
22	0.001			
23	0.006	0.014	40.92	Pass
24	0.001			
25	0.004	0.013	0.00	Pass
26	0.002			
27	0.004	0.013	0.00	Pass
28	0.001			
29	0.003	0.012	0.00	Pass
30	0.001			
31	0.003	0.011	0.00	Pass
32	0.001			
33	0.003	0.009	0.00	Pass
34	0.001			
35	0.003	0.010	0.00	Pass
36	0.001			
37	0.003	0.009	0.00	Pass
38	0.001			
39	0.002	0.009	0.00	Pass
40	0.001			

Note :

1. Dynamic limits were applied for this test. The highest harmonics values in the above table may not occur at the same window as the maximum harmonics/limit ratio.

2: According to EN61000-3-2 paragraph 7.4 the limits given in table 3 are valid for all applications having an active input power >75W.

3." -- " mean the limit is not applicable/

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Voltage Fluctuations and Flicker		


Flicker Test Summary (Run time)

Test Result: Pass

Status: Test Completed

Pst_i and limit line

European Limits



Time is too short for Plt plot

Parameter values recorded during the test:

Vrms at the end of test (Volt):	223.76		
Highest dt (%):	0.00	Test limit (%):	4.00
Highest dc (%):	0.00	Test limit (%):	3.30
Highest dmax (%):	0.00	Test limit (%):	4.00
Highest Pst (10 min. period):	0.001	Test limit:	1.000
Highest Plt (2 hr. period):	0.001	Test limit:	0.650


Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Power Harmonics (Classification : Class D)		

Test Result: Pass

Source qualification: Distortion


Current & voltage waveforms

It is 0.0% outside Class-D envelope



Harmonics and Class D limit line

European Limits



Test result: Pass

Worst harmonic was #3 with 98.77 % of the limit.

Current Test Result Summary (Run time)

Test Result: Pass

Source qualification: Distortion

Highest parameter values during test:

V_RMS (Volts): 224.01	I_RMS (Amps): 0.505
I_Peak (Amps): 1.208	Crest Factor: 2.509
I_Fund (Amps): 0.389	Power Factor: 0.765
Power (Watts): 87	

Harm#	Harmonics	Limit	% of Limit	Status
2	0.008			
3	0.287	0.291	98.77	Pass
4	0.006			
5	0.141	0.161	87.51	Pass
6	0.005			
7	0.049	0.081	60.39	Pass
8	0.003			
9	0.032	0.041	79.24	Pass
10	0.002			
11	0.018	0.029	61.24	Pass
12	0.002			
13	0.013	0.027	49.84	Pass
14	0.001			
15	0.010	0.023	44.98	Pass
16	0.002			
17	0.007	0.021	35.01	Pass
18	0.002			
19	0.007	0.018	39.01	Pass
20	0.002			
21	0.006	0.016	36.39	Pass
22	0.001			
23	0.005	0.014	36.68	Pass
24	0.001			
25	0.004	0.013	0.00	Pass
26	0.001			
27	0.004	0.013	0.00	Pass
28	0.001			
29	0.003	0.012	0.00	Pass
30	0.001			
31	0.003	0.011	0.00	Pass
32	0.001			
33	0.003	0.010	0.00	Pass
34	0.001			
35	0.002	0.010	0.00	Pass
36	0.001			
37	0.003	0.009	0.00	Pass
38	0.001			
39	0.002	0.009	0.00	Pass
40	0.001			

Note :

1. Dynamic limits were applied for this test. The highest harmonics values in the above table may not occur at the same window as the maximum harmonics/limit ratio.
2. According to EN61000-3-2 paragraph 7.4 the limits given in table 3 are valid for all applications having an active input power >75W.
3. -- " mean the limit is not applicable/

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Voltage Fluctuations and Flicker		


Flicker Test Summary (Run time)

Test Result: Pass

Status: Test Completed

Pst_i and limit line

European Limits



Time is too short for Plt plot

Parameter values recorded during the test:

Vrms at the end of test (Volt):	223.63		
Highest dt (%):	0.00	Test limit (%):	4.00
Highest dc (%):	0.00	Test limit (%):	3.30
Highest dmax (%):	0.00	Test limit (%):	4.00
Highest Pst (10 min. period):	0.001	Test limit:	1.000
Highest Plt (2 hr. period):	0.001	Test limit:	0.650

13.4. Test Data of Electrostatic Discharge

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Electrostatic Discharge (Performance Criteria: B)		

Test point	Polarity	Number of Discharges	Observation	Result
Seams	+/-8kV Air	10	Normal function	PASS
Switch	+/-4kV Air	50	Normal function	PASS
Knobs	+/-4kV Con	50	Normal function	PASS
Metal Plate	+/-4kV Con	50	Normal function	PASS
Screws	+/-4kV Con	50	Normal function	PASS
H.C.P.	+/-4kV	50	Normal function	PASS
V.C.P.	+/-4kV	50	Normal function	PASS

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Electrostatic Discharge (Performance Criteria: B)		

Test point	Polarity	Number of Discharges	Observation	Result
Seams	+/-8kV Air	10	Normal function	PASS
Switch	+/-4kV Air	50	Normal function	PASS
Knobs	+/-4kV Con	50	Normal function	PASS
Metal Plate	+/-4kV Con	50	Normal function	PASS
Screws	+/-4kV Con	50	Normal function	PASS
H.C.P.	+/-4kV	50	Normal function	PASS
V.C.P.	+/-4kV	50	Normal function	PASS

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

13.5. Test Data of Radiated Susceptibility

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Radiated Susceptibility (Performance Criteria: A)		

Frequency (MHz)	Position (Angle)	Polarity (H or V)	Field Strength (V/m)	Observation	Results
80-1000	0	H	3	Normal Function	Pass
80-1000	0	V	3	Normal Function	Pass
80-1000	90	H	3	Normal Function	Pass
80-1000	90	V	3	Normal Function	Pass
80-1000	180	H	3	Normal Function	Pass
80-1000	180	V	3	Normal Function	Pass
80-1000	270	H	3	Normal Function	Pass
80-1000	270	V	3	Normal Function	Pass

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Radiated Susceptibility (Performance Criteria: A)		

Frequency (MHz)	Position (Angle)	Polarity (H or V)	Field Strength (V/m)	Observation	Results
80-1000	0	H	3	Normal Function	Pass
80-1000	0	V	3	Normal Function	Pass
80-1000	90	H	3	Normal Function	Pass
80-1000	90	V	3	Normal Function	Pass
80-1000	180	H	3	Normal Function	Pass
80-1000	180	V	3	Normal Function	Pass
80-1000	270	H	3	Normal Function	Pass
80-1000	270	V	3	Normal Function	Pass

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

13.6. Test Data of Electrical Fast Transient

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Electrical Fast Transient (Performance Criteria: B)		

Inject Line	Polarity	Voltage kV	Inject Time (Second)	Inject Method	Observation	Result
L	±	1kV	60	Direct	Normal Function	Pass
N	±	1kV	60	Direct	Normal Function	Pass
PE	±	1kV	60	Direct	Normal Function	Pass
L+N	±	1kV	60	Direct	Normal Function	Pass
L+PE	±	1kV	60	Direct	Normal Function	Pass
N+PE	±	1kV	60	Direct	Normal Function	Pass
L+N+PE	±	1kV	60	Direct	Normal Function	Pass
LAN	±	0.5kV	60	Clamp	Normal Function	Pass
Telephone Line	±	0.5kV	60	Clamp	Normal Function	Pass

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Electrical Fast Transient (Performance Criteria: B)		

Inject Line	Polarity	Voltage kV	Inject Time (Second)	Inject Method	Observation	Result
L	±	1kV	60	Direct	Normal Function	Pass
N	±	1kV	60	Direct	Normal Function	Pass
PE	±	1kV	60	Direct	Normal Function	Pass
L+N	±	1kV	60	Direct	Normal Function	Pass
L+PE	±	1kV	60	Direct	Normal Function	Pass
N+PE	±	1kV	60	Direct	Normal Function	Pass
L+N+PE	±	1kV	60	Direct	Normal Function	Pass
LAN	±	0.5kV	60	Clamp	Normal Function	Pass
Telephone Line	±	0.5kV	60	Clamp	Normal Function	Pass

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

13.7. Test Data of Surge

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Surge (Performance Criteria: A)		

Inject Line	Polarity	Angle	Voltage kV	Time Interval (Second)	Inject Method	Observation	Result
L-N	±	0	1kV	60	Direct	Normal Function	Pass
L-N	±	90	1kV	60	Direct	Normal Function	Pass
L-N	±	180	1kV	60	Direct	Normal Function	Pass
L-N	±	270	1kV	60	Direct	Normal Function	Pass
L-PE	±	0	2kV	60	Direct	Normal Function	Pass
L-PE	±	90	2kV	60	Direct	Normal Function	Pass
L-PE	±	180	2kV	60	Direct	Normal Function	Pass
L-PE	±	270	2kV	60	Direct	Normal Function	Pass
N-PE	±	0	2kV	60	Direct	Normal Function	Pass
N-PE	±	90	2kV	60	Direct	Normal Function	Pass
N-PE	±	180	2kV	60	Direct	Normal Function	Pass
N-PE	±	270	2kV	60	Direct	Normal Function	Pass

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Surge (Performance Criteria: A)		

Inject Line	Polarity	Angle	Voltage kV	Time Interval (Second)	Inject Method	Observation	Result
L-N	±	0	1kV	60	Direct	Normal Function	Pass
L-N	±	90	1kV	60	Direct	Normal Function	Pass
L-N	±	180	1kV	60	Direct	Normal Function	Pass
L-N	±	270	1kV	60	Direct	Normal Function	Pass
L-PE	±	0	2kV	60	Direct	Normal Function	Pass
L-PE	±	90	2kV	60	Direct	Normal Function	Pass
L-PE	±	180	2kV	60	Direct	Normal Function	Pass
L-PE	±	270	2kV	60	Direct	Normal Function	Pass
N-PE	±	0	2kV	60	Direct	Normal Function	Pass
N-PE	±	90	2kV	60	Direct	Normal Function	Pass
N-PE	±	180	2kV	60	Direct	Normal Function	Pass
N-PE	±	270	2kV	60	Direct	Normal Function	Pass

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

13.8. Test Data of Conducted Susceptibility

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Conducted Susceptibility (Performance Criteria: A)		

Frequency Range (MHz)	Voltage Applied dBuV(V)	Inject Method	Tested Port of EUT	Observation	Result
0.15 ~ 80	130(3V)	CDN 1	AC IN	Normal Function	PASS
0.15 ~ 80	130(3V)	CDN 1	Signal Line	Normal Function	PASS

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Conducted Susceptibility (Performance Criteria: A)		

Frequency Range (MHz)	Voltage Applied dBuV(V)	Inject Method	Tested Port of EUT	Observation	Result
0.15 ~ 80	130(3V)	CDN 1	AC IN	Normal Function	PASS
0.15 ~ 80	130(3V)	CDN 1	Signal Line	Normal Function	PASS

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

13.9. Test Data of Power Frequency Magnetic Field

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Power Frequency Magnetic Field (Performance criteria: A)		

Polarization	Frequency (Hz)	Magnetic Strength (A/m)	Observation	Test Result
X Orientation	50	1	Normal Function	PASS
Y Orientation	50	1	Normal Function	PASS
Z Orientation	50	1	Normal Function	PASS

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Power Frequency Magnetic Field (Performance criteria: A)		

Polarization	Frequency (Hz)	Magnetic Strength (A/m)	Observation	Test Result
X Orientation	50	1	Normal Function	PASS
Y Orientation	50	1	Normal Function	PASS
Z Orientation	50	1	Normal Function	PASS

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could / could not be reset by operator at ____ kV.
 - No false alarms or other malfunctions were observed during or after the test.

13.10. Test Data of Voltage Dips and Interruption

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 1: Besteck, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Voltage Dips and Interruption		

Voltage Dips and Interruption Reduction(%)	Angle	Test Duration (Periods)	Required Performance Criteria	Observation	Test Result
>95(0V)	0	0.5	B	A	PASS
>95(0V)	45	0.5	B	A	PASS
>95(0V)	90	0.5	B	A	PASS
>95(0V)	135	0.5	B	A	PASS
>95(0V)	180	0.5	B	A	PASS
>95(0V)	225	0.5	B	A	PASS
>95(0V)	270	0.5	B	A	PASS
>95(0V)	315	0.5	B	A	PASS
30(161V)	0	25	C	A	PASS
30(161V)	45	25	C	A	PASS
30(161V)	90	25	C	A	PASS
30(161V)	135	25	C	A	PASS
30(161V)	180	25	C	A	PASS
30(161V)	225	25	C	A	PASS
30(161V)	270	25	C	A	PASS
30(161V)	315	25	C	A	PASS
>95(0V)	0	250	C	C	PASS
>95(0V)	45	250	C	C	PASS
>95(0V)	90	250	C	C	PASS
>95(0V)	135	250	C	C	PASS
>95(0V)	180	250	C	C	PASS
>95(0V)	225	250	C	C	PASS
>95(0V)	270	250	C	C	PASS
>95(0V)	315	250	C	C	PASS

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could be reset by operator.
 - No false alarms or other malfunctions were observed during or after the test.

Date of Test	Jan. 23, 2002	Test Room	No.3 Shielded Room
Test Mode	Mode 2: HEC, 1920*1440/75Hz	Product	Terminator P4
Test Condition	Voltage Dips and Interruption		

Voltage Dips and Interruption Reduction(%)	Angle	Test Duration (Periods)	Required Performance Criteria	Observation	Test Result
>95(0V)	0	0.5	B	A	PASS
>95(0V)	45	0.5	B	A	PASS
>95(0V)	90	0.5	B	A	PASS
>95(0V)	135	0.5	B	A	PASS
>95(0V)	180	0.5	B	A	PASS
>95(0V)	225	0.5	B	A	PASS
>95(0V)	270	0.5	B	A	PASS
>95(0V)	315	0.5	B	A	PASS
30(161V)	0	25	C	A	PASS
30(161V)	45	25	C	A	PASS
30(161V)	90	25	C	A	PASS
30(161V)	135	25	C	A	PASS
30(161V)	180	25	C	A	PASS
30(161V)	225	25	C	A	PASS
30(161V)	270	25	C	A	PASS
30(161V)	315	25	C	A	PASS
>95(0V)	0	250	C	C	PASS
>95(0V)	45	250	C	C	PASS
>95(0V)	90	250	C	C	PASS
>95(0V)	135	250	C	C	PASS
>95(0V)	180	250	C	C	PASS
>95(0V)	225	250	C	C	PASS
>95(0V)	270	250	C	C	PASS
>95(0V)	315	250	C	C	PASS

Criteria judgment of Test result:

- Meet criteria A: No abnormalities were observed during and directly after the test.
- Meet criteria B: Operate as intended after the test
- Meet criteria C: Loss/Error of function
- Additional Information
 - EUT stopped operation and could be reset by operator.
 - No false alarms or other malfunctions were observed during or after the test.

Attachment 1 : EUT Test Photographs

Attachment 1 : EUT Test Photographs

Front View of Conducted Test (Mode 1)



Back View of Conducted Test (Mode 1)



Front View of Conducted Test (Mode 2)




Back View of Conducted Test (Mode 2)



Front View of Radiated Test (Mode 1)




Front View of Radiated Test (Mode 1)



Back View of Radiated Test (Mode 2)



Back View of Radiated Test (Mode 2)




Harmonics Test Setup (Mode 1)



Harmonics Test Setup (Mode 2)



ESD Test Setup (Mode 1)



ESD Test Setup (Mode 2)



RS Test Setup (Mode 1)



RS Test Setup (Mode 1)



EFT/B Test Setup (Mode 1)



EFT/B Test Setup (Mode 2)



Surge Test Setup (Mode 1)



Surge Test Setup (Mode 2)



CS Test Setup (Mode 1)



CS Test Setup (Mode 2)



Power Frequency Magnetic Field Test Setup (Mode 1)



Power Frequency Magnetic Field Test Setup (Mode 2)



Dips Test Setup (Mode 1)



Dips Test Setup (Mode 2)



Attachment 2 : EUT Detailed Photographs

Attachment 2 : EUT Detailed Photographs


(1) EUT Photo




(2) EUT Photo




(3) EUT Photo




(4) EUT Photo




(5) EUT Photo



(6) EUT Photo



(7) EUT Photo




(8) EUT Photo




(9) EUT Photo




(10) EUT Photo



(11) EUT Photo



(12) EUT Photo



(13) EUT Photo



(14) EUT Photo



Reference : Laboratory of License